PROPOSED RESIDENTIAL SUBDIVISION

LOT 1 & 3 DP1309170, HERDSMEN ROAD, LOCHINVAR RIDGE ESTATE


CONCEPT CIVIL ENGINEERING DESIGN (FOR DEVELOPMENT APPLICATION)

CLIENT: LOCHINVAR RIDGE ESTATE PTY LTD


CONSENT AUTHORITY: MAITLAND CITY COUNCIL


DATE: MARCH 2025


DWG NO.	SHEET TITLE	REV
C00	COVER SHEET	1
C01	GENERAL ARRANGEMENT PLAN	1
C02	PLAN SHEET	1
C03	REGRADE & RETAINING WALL PLAN	1
C04	GENERAL NOTES & TYPICAL DETAILS	1
C05	EARTHWORKS PLAN	1
C06	SOIL AND WATER MANAGEMENT PLAN	1
C07	SOIL AND WATER MANAGEMENT DETAILS	1



					North	Scale		Designed	Scale	Client	
							COPYRIGHT	KS	1:100		
							Copyright in the drawings, information and data recorded hereon is the	Cad Refere		NEW BECINNINGS	
							and data recorded hereon is the			TTINYAR SUICE MAR	ENGINEEDING COULTIONS
							property of Geoff Craig & Associates Pty Ltd and may not be used, copied	24299C dC	00 r1	COCHINEAR INC. INT.	ENGINEERING SOLUTIONS
							or reproduced in whole or part for any	Project Apr	proval	COLOR RIDGE	A.B.N. 92 086 017 745
	1	ORIGINAL ISSUE JE	AS	10.03.25			purpose other than that for which it is supplied without the prior consent of Geoff Craig & Associates Pty Ltd.	IAN HILL (B.	E)		1 HARTLEY DRIVE, THORNTON NSW 2322 PO BOX 3337, THORNTON NSW 2322
REVI	ISION	Description Drawn	App'c	d Date			of Geoff Craig & Associates Pty Ltd.	Consulting Civ	vil Engineer		PHONE: (02) 4964 1811
PLO	T DAT	TE: 11/03/2025 5:45:15 PM CAD FILE: Q:\24\24299 Lochinvar Ridge, Sut	division	of Ex House	\02 CAD\AutoCAD\Civil\24299C d	00 r1.dwg					








NOTES:

- 1. ALL DIMENSIONS OF EASEMENTS AND LOTS ARE SUBJECT TO REGISTRATION OF DEPOSITED PLAN.
- 2. ALL WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH THE APPROVED PLANS SUBJECT TO MAITLAND CITY COUNCIL'S MANUAL OF ENGINEERING STANDARDS.
- EROSION CONTROL DEVICES AND SILTATION TRAPS TO BE INSTALLED BEFORE SITE IS DISTURBED IN ACCORDANCE WITH THE ATTACHED EROSION AND SEDIMENTATION CONTROL PLAN. COUNCIL IS TO INSPECT ALL EROSION AND SEDIMENT CONTROLS PRIOR TO ANY WORK COMMENCING.
- 4. DENUDED AREAS TO BE SEEDED IMMEDIATELY UPON COMPLETION OF TOP SOIL SPREADING
- 5. ALL REINFORCED CONC. STORMWATER DRAINAGE PIPES ARE TO BE RUBBER RING JOINTED.
- 6. ALL EKI PIT GRATES TO BE SADDINGTONS GGLCD OR SIMILAR WITH RHS FRONT AND BACK.
- ALL PITS DEEPER THAN 12m ARE TO BE CONSTRUCTED WITH STEP IRONS IN ACCORDANCE WITH MCC MANUAL OF ENGINEERING STANDARDS STD DWG SD039, SD033 AND ARE TO HAVE INCREASED INTERNAL DIMENSIONS TO ALLOW ACCESS IN ACCORDANCE WITH CONFINED SPACE REGULATIONS.
- ALL STREET DRAINAGE PITS TO BE CONSTRUCTED IN ACCORDANCE WITH SD039
- ALL INTERALLOTMENT DRAINAGE PIPES TO BE SEWER GRADE UPVC (UNLESS OTHERWISE SHOWN) OR AN APPROVED EQUIVALENT. THE MINIMUM SLOPE OF INTERALLOTMENT DRAINAGE LINES SHALL BE 1%, THE 9. INTERALLOTMENT DRAINAGE LINE SHALL BE A MINIMUM OF 0.5m FROM THE BOUNDARY AND LOCATED IN AN EASEMENT 1.5m WIDE.
- 10. JUNCTION PITS SHALL BE PROVIDED WHERE AN INTERALLOTMENT PIT IS NOT CONSTRUCTED. THEY SHALL BE 1.0m FROM THE ADJOINING DOWNSTREAM ALLOTMENT BOUNDARY.
- 11. ALL EXISTING UNDERGROUND SERVICES MUST BE LOCATED AND EXPOSED PRIOR TO EARTHWORKS COMMENCING AND IT IS THE RESPONSIBILITY OF THOSE PERSONS USING THIS PLAN TO CONFIRM BOTH POSITION & LEVEL OF THESE UTILITIES IN CONJUNCTION WITH THE APPROPRIATE AUTHORITY.
- 12. SUBSOIL DRAINS ARE TO BE PROVIDED IN ACCORDANCE WITH COUNCIL'S STD DWG SD035 AND SD032, AND WHERE NECESSARY, AS DIRECTED BY COUNCIL DURING WORKS.
- 13. PAVEMENT THICKNESS TO BE IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE APPROVED GEOTECHNICAL REPORT.
- 14. EASEMENT FOR BATTER TO BE CREATED WHERE FILL BATTERS ARE 3(H):1(V) OR STEEPER OR WHERE DEPTH OF FILL AT BOUNDARY EXCEEDS 600mm.
- 15. WORKING HOURS ON SITE SHALL BE IN ACCORDANCE WITH EPA & COUNCIL REQUIREMENTS.
- 16. VEHICULAR ACCESS AND ALL SERVICES ARE TO BE MAINTAINED AT ALL TIMES TO ADJOINING PROPERTIES AFFECTED BY CONSTRUCTION WORKS.


FINISHED GROUND

LEVEL


- 17. MAINTENANCE ON THE SEEDED AND TURFED AREAS SHALL BE OVER A 3 MONTH PERIOD. TURF THE FULL WIDTH OF ALL EARTH DISH DRAINS. LAY 600mm WIDE TURF STRIPS TO EACH SIDE OF CONCRETE ACCESSWAYS, PATHWAYS, AT THE REAR OF ALL KERB AND GUTTERING AND AT THE TOP OF CUT BATTERS MULCH (IF AVAILABLE FROM SITE (LEARING) AND SEED ALL OTHER DISTURBED AREAS INCLUDING TRENCHES. NO PERMANENT MULCH/WOODCHIP IS PERMITTED WITHIN FLOWPATHS AND PUBLIC AREAS
- ALL PERAMBULATOR RAMPS TO BE CONSTRUCTED AS SHOWN ON PLANS AND IN ACCORDANCE WITH MAITLAND CITY COUNCIL'S MANUAL OF ENGINEERING STANDARDS STD DWG SD019.
- 19. TRAFFIC CONTROL MEASURES TO BE IN ACCORDANCE WITH AS 1742.3-1996.
- 20. ALL LEVELS MUST BE OBTAINED FROM ESTABLISHED BENCH MARKS AS DIRECTED BY THE SUPERVISOR
- 21. THE CONTRACTOR IS TO ENSURE THAT ALL THE NECESSARY SERVICE PIPE CONDUITS AND FITTINGS ARE IN PLACE PRIOR TO THE FINAL WEARING COURSE BEING LAID.
- 22. PROVIDE STREET NAME SIGNS AT ALL INTERSECTIONS, DOUBLE BLADED WHERE NECESSARY IN ACCORDANCE WITH MCC MANUAL OF ENGINEERING STANDARDS STD DWG SD029.
- 23. ALL SITE FILLING TO BE CONTROLLED FILL WITH INSPECTION TESTING TO BE CARRIED OUT BY A NATA REGISTERED LABORATORY TO LEVEL 1 IN ACCORDANCE WITH AS3798
- 24. PAVEMENT PROOF ROLLING AND LEVEL CHECKS, DENSITY AND BENKELMAN BEAM TESTING TO BE IN ACCORDANCE WITH COUNCIL'S MANUAL OF ENGINEERING STANDARDS.
- 25. WHERE APPROVED CONSTRUCTION WORK REQUIRES THE REMOVAL OF TREES, THE CONTRACTOR IS TO ENGAGE THE SERVICES OF A SUITABLY QUALIFED ECOLOGIST TO INSPECT THE SITE AND IDENTIFY ANY TREE WHICH IS LIKELY TO BE A HABITAT TREE. THE ECOLOGIST IS ALSO TO BE ON SITE DURING THE FELLING OF ANY IDENTIFIED TREE AND ENSURE THAT ANY DISPLACED OR INJURED WILDLIFE IS COLLECTED AND FORWARDED TO AN APPROPRIATE WILDLIFE RESCUE SERVICE. THE ECOLOGIST IS TO REPORT TO COUNCIL ON ACTION TAKEN AS PART OF TREE CLEARING OPERATIONS.




					North	Scale				Client	
					North	Scule		Designed	Scale	Chent	
							COPYRIGHT	ĸs	1:20		
							Copyright in the drawings, information	113		NBW BEGINNINGS	
							and data recorded hereon is the	Cdd Referei	nce	COCHUNHAR THE AND	
							property of Geoff Craig & Associates	21.200C dC	0/1	Continue	ENGINEERING SOLUTIONS
							Figure and may not be used, copied		0411	Dince	
							or reproduced in whole or part for any	Project App		COCTATA RUBER	A.B.N. 92 086 017 745
1	ORIGINAL ISSUE	JE	AS	10.03.25			purpose other than that for which it	IAN HILL (B.	E)	66	1 HARTLEY DRIVE, THORNTON NSW 2322
			1				is supplied without the prior consent of Geoff Craig & Associates Pty Ltd.				P0 B0X 3337, THORNTON NSW 2322
REVISION	Description	Drawn	App'd	Date			of Geoff Graig & Associates Fty Lta.		5		PHONE: (02) 4964 1811
PLOT DA	TE: 11/03/2025 5:45:21 PM CAD FILE: Q:\24\24299 Lochinvar Ri	idae. Sub	odivision o	f Ex House\	02 CAD\AutoCAD\Civil\24299C d	04 r1.dwa				•	



PLOT DATE: 11/03/2025 5:45:24 PM CAD FILE: Q:\24\24299 Lochinvar Ridge, Subdivision of Ex House\02_CAD\AutoCAD\Civil\24299C dC05 r1.dwg








TYPICAL CONSTRUCTION SCHEDULE

		WEEK						
	1	2	3	4	5	6	7	8
CONSTRUCT ALL TEMPORARY SEDIMENT BASINS								
PLACE SILT FENCE ALONG ROAD BOUNDARIES AS SHOWN								
PLACE SILT FENCE BELOW AREAS TO BE REGRADED								
CONSTRUCT ALL DIVERSION BANKS CATCHING CLEAN WATER								
ROAD CONSTRUCTION AND REGRADING								
PLACE SILT FENCE AROUND TOPSOIL STOCKPILES								
PLACE SEDIMENT BARRIERS AROUND STORMWATER PITS AT COMPLETION OF DRAINAGE								
PLACE STRIP TURF PARALLEL TO DESIGN CONTOURS ALONG ROAD AS SHOWN								



Consulting Civil Engineer

REVISION Drawn App'd Date CAD FILE: Q:\24\24299 Lochinvar Ridge, Subdivision of Ex House\02_CAD\AutoCAD\Civil\24299C dC07 r1.dwg PLOT DATE: 11/03/2025 5:45:27 PM

Description

EROSION CONTROL

- EROSION CONTROL DEVICES AND SILTATION TRAPS TO BE INSTALLED BEFORE SITE IS
 DISTURBED IN ACCORDANCE WITH N.S.W. DEPARTMENT OF CONSERVATION AND LAND
 MANAGEMENT SUDDELINES AND APPROVED BY COUNCIL INSPECTOR.
 ALL PERMETER AND CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST
 STEP IN EARTHWORKS AND/OR CLEARING.
 SILT TO BE REMOVED FROM TEMPORARY SEDIMENT CONTROL BASINS AS DIRECTED BY
 COUNCIL INSPECTOR OR DEPARTMENT OF LAND AND WATER CONSERVATION
 REPRESENTATIVE TO MAINTAIN SILTATION STORAGE CAPACITY IN TEMPORARY BASINS.
 EIL TO ADIE ADIE ADIE CONSERVATION SILTATION STORAGE CAPACITY IN TEMPORARY BASINS.
- 4. FILTRATION BUFFER ZONES ARE TO BE FENCED OFF AND ACCESS PROHIBITED TO ALL PLANT ΑΝΠ ΜΑΓΗΙΝΕΡΥ
- AND MACHINERY. HAY BALE BARNIERS AND GEOFABRIC FENCES ARE TO BE CONSTRUCTED TO TOE OF BATTER PRIOR TO COMMENCEMENT OF EARTHWORKS IMMEDIATELY AFTER CLEARING OF VEGETATION BEFORE REMOVAL OF TOPSOIL. SANDBAGS TO BE USED DURING ROAD CONSTRUCTION TO DIVERT STORMWATER INTO PITS WHEN SUBGRADE IS UP TO KERB LEVEL. ALL TEMPORARY EARTH BERNS, DIVERSION AND SILT DAM EMBANKMENTS ARE TO BE MACHINE COMPACTED, SEEDED & MULCHED FOR TEMPORARY VEGETATION COVER AS SOON AS THEY HAVE BEEN FORMED. 5.
- 6. 7.

- IMALINING LOWITAALTEU, SEEDED & MULLHED TWI TEMPURARY VEGETATION COVER AS SOON AS THEY HAVE BEEN FORMED.
 CLEAN WATER IS TO BE DIVERTED AWAY FROM DISTURBED GROUND AND INTO DRAINAGE SYSTEM.
 ALL SEDIMENT TRAPPING STRUCTURES AND DEVICES ARE TO BE INSPECTED AFTER STORMS FOR STRUCTURAL DAMAGE OR CLOGGING. TRAPPED MATERIAL IS TO BE REMOVED TO A SAFE APPROVED LOCATION.
 ALL TOPSOIL IS TO BE STOCKPILED ON SITE FOR RE-USE (AWAY FROM TREES AND DRAINAGE LINES). MEASURES SHALL BE APPLIED TO PREVENT ERSOIND OF THE STOCKPILES.
 ALL FULLS ARE TO BE LEFT WITH A LIP AT THE TOP OF THE SLOPE AT THE END OF EACH DAYS EARTHWORKS. THE HEIGHT OF THE LIP SHALL BE A MINIMUM OF 200mm.
 ALL CUT AND FILL SLOPES ARE TO BE SEEDED AND MULCHED WITHIN 10 DAYS OF COMPLETION OF FORMATION.
 UNDERSCRUBBING OF VEGETATION TO BE RESTRICTED TO SLASHING TO MINIMISE SOIL DISTURBANCE.
 UPON OFFORMATION.
 UNDERSCRUBBING OF VEGETATION TO BE RESTRICTED TO SLASHING TO MINIMISE SOIL DISTURBANCE.
 UPON OFFORMATION FALL EARTHWORKS OR AS DIRECTED BY COUNCIL, SOIL CONSERVATION TREATMENTS SHALL BE APPLIED TO RENDER AREAS THAT HAVE BEEN DISTURBED, EROSION PROFE WITHIN 14 DAYS.
 DENDER AREAS TIO DE STRUPTURED OR HYDROMULCH SEEDED WITH THE SEED MIX BELOW

- 15. DENUDED AREAS TO BE STRIP TURFED OR HYDROMULCH SEEDED WITH THE SEED MIX BELOW DENOTE ALLAS TO DE STIM FORD DO ATTRONOCCI SELEDO MITTAL SECONDA DECOM NOR APPROVED BY DEPARTMENT OF LAND AND WATER CONSERVATION REPRESENTATIVE, WITHIN 14 DAYS OF PRACTICAL COMPLETION OF EARTHWORKS. STRIPS ARE TO BE PLACED ACROSS THE CONTOUR AT RIGHT ANGLES TO THE DIRECTION OF SLOPE.

	HYDROMUL	CH SEEDMIXES	
SUM	IMER MIX	AUTI	JMN MIX
MATERIAL	APPLICATION RATE	MATERIAL	APPLICATION RATE
JAPANESE MILLET COUCH CARPET GRASS HAIFA WHITE CLO BINDER PULP FERTILISER	10 Kg/Ha 10 Kg/Ha	OATS RYE GRASS RED CLOVER WHITE CLOVER COUCH FERTILISER ENRICH OR DYNAMIC LIFTER	20 Kg/Ha 10 Kg/Ha 5 Kg/Ha 10 Kg/Ha 10 Kg/Ha IER 300 Kg/Ha 1000Kg/Ha

- THE AREA OVER ALL STORMWATER AND SEWER LINES NOT WITHIN ROAD RESERVES IS TO BE MULCHED AND SEEDED WITHIN 14. DAYS AFTER BACKFILL
 NO MORE THAN 150m OF TRENCH IS TO BE OPEN AT ANY ONE TIME.
 AREAS OVER ELECTRICITY, TELEPHONE AND GAS SUPPLY TRENCHES ARE TO BE SEEDED AND MULCHED BY THE RELEVANT AUTHORITY WITHIN 14. DAYS AFTER BACKFILL.
 ALL FOOTPATHS, BERMS AND BATTERS AND SITE REGRADING AREAS ARE TO BE TOPSOILED WITH MINIMUM 75mm OF SELECTED SITE TOPSOIL AND GRASSED.
 STRIPS OF TURF ARE TO BE PLACED IMMEDIATELY BEHIND THE KERB AND GUTTER ON ALL NEW ROADS AND AT LOCATIONS AS DETERMINED BY COUNCL'S SUPERVISING OFFICER.
 ALL FOODPEVENTION MEGUREED VECTORS THE GRASSING MEDICED SUPERVISING OFFICER.
- 21. ALL FINAL EROSION PREVENTION MEASURES INCLUDING THE ESTABLISHMENT OF GRASSING ARE TO BE COMPLETED PRIOR TO THE SUBDIVISION FINAL INSPECTION. ALL EROSION DEVICES ARE TO BE MAINTAINED UNTIL THE END OF THE MAINTENANCE PERIOD.

	IMINARY IS	SUE
PROPOSED RESIDENTIAL SUBDIVISION OT 1 & 3 DP13079170 (HERDSMEN ROAD)	Project No 2429	90
LOCHINVAR RIDGE ESTATE	Drawing No	Revision
SOIL AND WATER MANAGEMENT DETAILS	C07	1
	A1 SHE	ET

1 O T

PHONE: (02) 4964 1811